



Public Works Engineering Division · 555 Santa Clara Street · Vallejo · CA · 94590 · 707.648.5251

**PROJECT UPDATE:** January 26, 2016

**FOR MORE INFORMATION:**

Srinivas Muktevi, Associate Civil Engineer, [Srinivas.Muktevi@cityofvallejo.net](mailto:Srinivas.Muktevi@cityofvallejo.net)

**MARE ISLAND WESTERN APPROACH REPLACEMENT BRIDGE PROJECT –BRIDGE OPENING ON FEBRUARY 01, 2016**

VALLEJO, CA – The Polyester concrete to match new deck with old deck and traffic lane striping has been completed, Contractor will complete miscellaneous items of work to open the bridge on February 1<sup>st</sup>, 2016. The bridge replacement completed with only one day closure of the Mare Island causeway.

Project Description: The Mare Island West Approach replacement project began on July 6, 2015. This project replaces a 50-foot section of original timber-trestle carried out in two stages in order to maintain one-way traffic coming onto Mare Island. The traffic exiting Mare Island directed through North Mare Island and out to State Highway 37.

During the construction, Pedestrian traffic has been detoured onto the temporary path over the Railroad Bridge. Now the Pedestrian traffic restored back onto the new sidewalk of the bridge to G Street.

Emergency response vehicles able to enter and exit Mare Island using the Causeway Bridge throughout the construction.

City published regular construction updates through the [City Manager's Bi-Weekly Report](#) and on the [project webpage](#).



**Project Milestones:**

Construction began: July 6<sup>th</sup> 2015 (one-way traffic on bridge)

Bridge opening: February 1<sup>st</sup>, 2016

< END >